ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Dated 15th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 8th June 1929, for restoring Manigatta Gollahalli Tank, Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees six hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for restoring Manighatta Gollahalli Tank, Mulbagal Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7 The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in exess or lower than the estimate will not be accepted.

Abstract estimate of restoring Manighatta Gollahalli Tank, Mulbagal Taluk :—

No.	Items of work	Per	Rate	Quantity	Cost	Total
	Bund R. L. 56·00		Rs. a. p.		Rs.	
1	Earthwork watering and tamping, etc., complete with 1/5th of the quantity of gravel admixture with lead and lift.	C.yd.		4,820		
2	Cutting grips for breach filling ...	,,		10		
3	Puddle wall in breach	,,		74		
4	Turfing	Sqr.		5,802		
5	Removing and resetting old stone ..	C.yd.		1,233		
6	New stone revetment	,,		1,795		
7	Gravel backing 6″ thick for revetment ...	...		833		
8	Grade stones cutting figures and painting	No.		35		
9	Index stones	,,		35		
10	Registered No. stone	,,		1		
11	Gauge stone	,,		1		
12	B. M. stones	,,		2		
13	Clearing jungle and prickly pier, etc. ...	Grade		34		
	Total to Bund ...	...				
	Sluice R. L. 43·00					
1	Earthwork excavation	C.yd.		90		
2	Refilling the earth with consolidation ...	,,		61		
3	Concrete in surki mortar	C.ft.		342		
4	Burnt brick in surki mortar ..	,,		732		
5	Burnt stone slabs 6″ thick	Sq.ft.		322		
6	Plastering with surki mortar... ...	Sqr.		4·16		
7	Providing plug and rod with locking arrangements	L. S.		...		
8	Drilling holes in cross orifice slabs, etc. ...	L. S.		...		
	Total to Sluice ...	...		...		

No.	Items of work	Per	Rate	a.	p.	Quantity	Cost	Total
	Left waste weir R. L. 50·00.		Rs.				Rs.	
1	Earthwork excavation and using to bund	C.yd.				206		
2	Surki mortar concrete	C.ft.				675		
3	Burnt brick in surki mortar	,,				2,258		
4	Burnt stone slabs 6″ thick	Sq.ft.				713		
5	Plastering with surki mortar ...	Sqr.				22·35		
6	New stone work...	C.yd.				210		
7	Providing joggle joints	Each				24		
8	Draft clearing and using the earth to bund.	C.yd.				810		
	Total to left weir Rs. ...	...	...			..		
	Right waste weir. R. L. 50·00.							
1	Earthwork excavation	C.yd.				253		
2	Surki mortar concrete	C.ft.				1,006		
3	Burnt brick in surki mortar ...	,,				2,843		
4	Burnt stone slabs 6″ thick	S.ft.				447		
5	Plastering with surki mortar ...	Sqr.				41·00		
6	New stone work	C.yd.				250		
7	Resetting old stone revetment ...	,,				83		
8	Proving joggle joints	Each				17		
9	Rough stone filling in below apron for scour.	C.yd.				204		
	Total to right weir ...	...				...	...	
	Constructing an acqueduct at left waste weir halla.	L. S.				...	...	
	Total ...	...	...			...	...	
	Contingencies at ...	...	...			...	...	
	Grand Total ...	..						

Notice dated 10th May 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, pages 441-442, dated 16th May 1929 calling for tenders for Restoring Perumachanahalli Minor Tank, Regd., No. 427-454 Chintamani Taluk.

Last date to tender is 1st June 1929.

Notice dated 8th May 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette* Part IV, pages 428 and 429, dated 16th May 1929, calling for tenders for contstructing a building for the District Board Office at Kolar.

Last date of tender is 1st June 1929.

Notification dated 17th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 8th June 1929 for restoring Bairanahalli Sheikmanpur Tank, Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees two hundred only in cash or Government Promissory Notes, as earnest money and be superscribed " Tender for restoring Bairanahalli Sheikmanpur, Malur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Detailed abstract estimate of restoring Bairanahalli, Sheikanpur Tank Reg. No. 35, Malur Taluk.

Items of work	Per	Quantity	Rate
			Rs.
Bund.			
Earthwork watering and tamping including lead and lift ...	C.yd.	6,610	
Turfing to bund	S.yd.	2,706	
New stone work	C.yd.	500	
Providing and fixing grade and index stones including chiselling and painting.	Each	12	
Register number stone with survey and constructive details.	,,	1	
B. M. stones	,,	2	
Gauge stones	,,	1	
Breach portion.			
Clearing debry and cutting grips	Lump	sum	
Earthwork excavation	C.yd.	10	
Concrete in surki mortar	C.ft.	52	
Burnt brik in surki mortar	,,	213	
Gravel backing	C.yd.	54	
Total to Bund ...	...	...	
Sluice.			
Earthwork	C.yd.	48	
Concrete in surki mortar	C.ft.	270	
Burnt brick in surki mortar	,,	142	
Plastering with surki mortar	Sqr.	4·41	
Burnt stone slabs (6" thick)	S.ft.	200	
Cutting holes for orifice and cross slabs	Each	4	
Providing plug and rod locking arrangement ...	Lump	sum	
Total to Sluice ...	...	...	

Items of work	Per	Quantity	Rate
Constructing waste weir at R. L. 50·00.			Rs.
Benching rock	Lump sum		
Excavating foundation earthwork	C.yd.	9	
Fixing foundation in concrete	C.ft.	103	
Burnt brick in surki mortar	,,	233	
Burnt stone slabs 4" to 6" thick	S.ft.	98	
Plastering with surki mortar	Sqr.	3·00	
New stone work	C.yd.	47	
Providing Joggles	Each	14	
Total of waste weir ...	..	...	

Dated 17th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 8th June 1929, for increasing the capacity of Pombarahalli, Byalakere, Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed, "Tender for increasing the capacity of Pombarahalli, Byalakere, Mulbagal Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for increasing the capacity of Pombarahalli-Bylakere Tank Reg. No 770 of Mulbagal Taluk.

Particulars	Per	Quantity	Rate
BUND AT R. L. 58·00.			Rs.
Earthwork to bund watering and tamping including lead and lift.	C.yd.	11,226	
Turfing	S.yd.	10,677	
Supplying and fixing grade stones including cutting figures and painting, etc.	Each	17	
Chiselling figures, painting and refixing old grade stones ...	,,	28	
Jungle clearing	Lump	sum	
Cutting trenches in old bund for grips of new earth ...	Grade	32	
Removing and resetting old stone revetment with new jelly	Lump	sum	
New stone revetment with new jelly	C.yd.	956	
Gravel backing behind revetment	,,	316	
Chistling and painting old Registered No. stone ...	Each	1	
Providing a gauge stone including cutting figures and painting, etc.	,,	1	
Total of bund ...	...	..	

Particulars	Per	Quantity	Rate
			Rs.
SLUICES.			
Petty repairs and providing plug and rod with locking arrangements.	Each Sluice	2	
Total of sluices ...	...	...	
WASTE WEIR AT R. L. 53·00.			
Removing and resetting coping slab in surki mortar ...	S.ft.	191	
Burnt brick in surki mortar	C.ft.	1.322	
Plastering with surki mortar	Sqr.	14·19	
Concrete in surki mortar	C.ft.	56	
Removing and resetting a pron	C.yd.	25	
New stone revetment (laterite)	,,	2	
Total of waste weir ...	...	...	
CONSTRUTCING A ROUGH STONE SILT DAM FOR THE APPROACH HALLA.			
Earthwork excavation	C.yd.	346	
Rough stone work dry	,,	81	
Filling with jelly the hollow portion between the crest and ground level of apron front and rear	Lump	sum	
Total ...	..	...	
Total of all ...	...	...	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

WATER SUPPLY DIVISION, BANGALORE.

Abstract Notification, dated 10th May 1929.

The attention of the public is invited to the detailed notification called for sealed tenders for laying 5" & 4" main from the Pump House at the foot of Lalitadri to the proposed Balancing Tank at the top of Lalitadri for Water Supply to New Guests Mansion, Mysore, published on pages 427-428 of Part IV of the *Mysore Gazette*, dated 16th May 1929.

The last day of the receipt of tenders is 21st May 1929.

B. R. GARUDACHAR,
Executive Engineer.

TUMKUR DIVISION.

Dated 15th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M., of 12th June 1929, for constructing Dalvoy tank near Singadahalli, Chiknayakanhalli Taluk, within half a mile of 14th mile of Chiknayakanhalli-Hagalvadi Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. *The plans* and detailed estimate may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Office of the Executive Engineer.

4. Each tender must be accompanied by a deposit of Rs. 3,000 only in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing Dalvoy tank, near Singadahalli, Chiknayakanhalli Taluk" in default of which, tenders will be rejected.